

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25674-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 23-14S-16W  
330 feet from S Section Line, 1500 feet from W Section Line  
Lease Name: FURTHMYER Well #: 3  
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 4787  
Op Name: DENNING, TOM DBA T. D. I. OIL OPER  
Address: 1310 BISON RD  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		

\$ 113.75

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/21/2007 3:00 PM  
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING  
Proposal Rcvd. from: ELDO Company: ANDERSON, C. D. DBA ANDERSON Phone: (785) 216-0694

Proposed Plugging Method: Ordered 195 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS  
Date/Time Plugging Completed: 09/21/2007 5:30 PM

WitnessType: NONE  
KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3365' w/25 sxs.  
2nd. Plug at 1002' w/25 sxs.  
3rd. Plug at 405' w/80 sxs.  
4th. Plug at 272' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.

Perfs:

INVOICED  
DATE 9/27/07  
INV. NO. 2008060497

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 25 2007

CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

Form CP-2/3

SEP 24 2007