

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4

December 2003

Type or Print on this Form

Form must be Signed

All blanks must be Filled

Lease Operator: American Warrior Inc.

Address: P.O. Box 399, Garden City Ks. 67846

Phone: (620) 272-1023 Operator License #: 4058

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8/24/07 (Date)

by: Rich Williams (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Topeka Depth to Top: 2917' Bottom: 2919' T.D. 3453'

Toronto Depth to Top: 3156' Bottom: 3158' T.D. 3453'

Lansing/KC Depth to Top: 3241' Bottom: 3439 T.D. 3453'

API Number: 15 - 163-19265-0001

Lease Name: Westhusin

Well Number: #1

Spot Location (QQQQ): C - NW - NE - SE

2310' Feet from ☐ North / ☒ South Section Line

990' Feet from ☒ East / ☐ West Section Line

Sec. 13 Twp. 9S S. R. 17W ☐ East ☒ West

County: Rooks

Date Well Completed: 6/20/63

Plugging Commenced: 8/27/02

Plugging Completed: 8/27/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Topeka	Oil	surface	255' 225'	85/8	255' 225'	0
Toronto	oil	surface	3453'	41/2	3453'	0
Lansing/KC	oil					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Log Tech perf 1775'. 1300', 825', 4spf. Ran tbg to 2490', Swift hooked up and pumped 150sx 60/40 4% gell possw/200# hulls, Pulled tbg to 1780', Swift hooked up and pumped 100sx 60/40 possw/4% gel and 200# hulls. Pulled tbg to 1300', Swift hooked up and pumped 100sx 60/40 possw/4% gel and 200# hulls. Pulled tbg to 600', Swift hooked up and pumped 150sx 60/40 possw/4% gel and 600# hulls. Pulled tbg.

Swift hooked up to 85/8 and pumped 50sx 60/40 possw/4% gel. Topped 41/2 off.

Name of Plugging Contractor: Swift Services inc

License #: 32382


Address: P.O. box 466 Ness City Kansas 67560

Name of Party Responsible for Plugging Fees: American Warrior Inc.

State of Kansas County, Finney, ss.

Jody Smith

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath; says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature)

(Address) P.O. Box 399 Garden City Kansas 67846

SUBSCRIBED and SWORN TO before me this 10 day of September, 2007

Erica Kuhlmeier
Notary Public

My Commission Expires: 09/22/09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

SEP 12 2007

KCC WICHITA

PKG