

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Woolsey Operating Company

Address: 125 N. Market, #1000, Wichita, KS 67202

Phone: (620) 886-5606

Operator License #: 5929 33168

Type of Well: Oil
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)

Docket #: KCC Pkt 10/21/07 per CP 1/3
(If SWD or ENHR)

The plugging proposal was approved on: 02/28/2007 (Date)

by: Steve Pfiefer (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top:	Bottom:	T.D.
<u>3425</u>	<u>3432</u>	<u>3490</u>
_____	_____	_____
_____	_____	_____

API Number: 15-00700658-00-01

Lease Name: Gilmore

Well Number: 1-OWWO

Spot Location (QQQQ): _____ - 100' N - SW - NW

1800 Feet from ☒ North / ☐ South Section Line

660 Feet from ☐ East / ☒ West Section Line

Sec. 36 Twp. 32 S. R. 12 ☐ East ☒ West

County: Barber

Date Well Completed: 07/21/2005

Plugging Commenced: 03/01/2007

Plugging Completed: 03/02/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4	291	None
				4 1/2	3521	2900

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

(3/1) Move in, rig up, set CIBP at 3370', (3/5) spot 2 sacks portland with dump bailer, rig up casing tools, stretch and cut pipe at 3000' and 2900' came free at 2900', (3/2) pull 4 1/2 casing down, run 2 3/8 tubing to 600', Allied load hole with 10 sacks gel pump 50 sacks 60/40 POZ 6% gel, pull tubing to 320', pump 80 sacks, pull to 40', load to surface, RDMO

Name of Plugging Contractor: Clarke Corporation

License #: 5105

RECEIVED
KANSAS CORPORATION COMMISSION

Address: P.O. Box 187, Medicine Lodge, KS 67104

SEP 27 2007


Name of Party Responsible for Plugging Fees: Woolsey Operating Company

State of Kansas County, Barber, ss.

CONSERVATION DIVISION
WICHITA, KS

John Swinford

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John Swinford

(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 26 day of September, 20 07

Glenda Morrison
Notary Public

My Commission Expires: 11/30/10

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202