

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Woolsey Operating Company
Address: 125 N. Market, #1000, Wichita, KS 67202 *PJT KCC*
Phone: (620) 886-5606 Operator License #: 5928 33108
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 03/02/2007 (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: 4660 Bottom: 4666 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-007-229^b18-0000
Lease Name: Bartholow
Well Number: B-1
Spot Location (QQQQ): C - SW - SW - SE *Per CP 2/3 PJT 10/2/07*
330 Feet from North / South Section Line
1980 Feet from East / West Section Line
Sec. 35 Twp. 32 S. R. 12 East West
County: Barber
Date Well Completed: 03/23/2006
Plugging Commenced: 03/2/2007
Plugging Completed: 03/06/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4	239	None
				4 1/2	4784	3300

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


(3/2) Move in, rig up, Log tech set CIBP at 4610', (3/5) spot 2 sacks portland with dump bailer, rig up casing tools, stretch and cut pipe at 3300', start casing out (3/6) pull casing down, run 2 3/8 tubing to 600', Allied load hole with 10 sacks gel pump 50 sacks 60/40 POZ 6% gel, pull tubing to 270', pump 80 sacks, pull to 40', load to surface, RDMO

Name of Plugging Contractor: Clarke Corporation License #: 5105 **RECEIVED**
KANSAS CORPORATION COMMISSION

Address: P.O. Box 187, Medicine Lodge, KS 67104 **SEP 27 2007**

Name of Party Responsible for Plugging Fees: Woolsey Operating Company
State of Kansas County, Barber, ss.

John Swinford
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John Swinford
(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 26 day of September, 20 07

Glenda Morrison My Commission Expires: 11/30/10
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PJT