

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Woolsey Operating Company  
Address: 125 N. Market, #1000, Wichita, KS 67202  
Phone: (620) 886-5606 Operator License #: 5929  
Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 6/25/2007 (Date)  
by: Steve Pfeifer (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: 4560 Bottom: 4570 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: 4490 Bottom: 4496 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-007-16660-00-00  
Lease Name: Mills  
Well Number: 1  
Spot Location (QQQQ): \_\_\_\_\_ - \_\_\_\_\_ - SW - SW  
660 Feet from  North /  South Section Line  
660 Feet from  East /  West Section Line  
Sec. 19 Twp. 32 S. R. 13  East  West  
County: Barber  
Date Well Completed: 01/20/2006  
Plugging Commenced: 06/26/2007  
Plugging Completed: 07/03/2007


Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				13 3/8	255	None
				5 1/2	4690	1100

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU, log tech set CIBP at 4440, spot 2 sacks portland with dump bailer 6/26 - rig up casing tools, stretch and cut  
6/27 - cut off at 1100' 7/3 - run 600' 2 3/8 tubing, Allied load hole with 15 sacks get, 300 hulls, spot 50 sacks  
pull tubing to 280', spot 100 sacks 60/40 POZ, 6% gel, pull to 60', load to surface, RDMO, top off 30' sand and 3 sacks crete

Name of Plugging Contractor: Clarke Corporation License #: 5105  
Address: P.O. Box 187, Medicine Lodge, KS 67104  
Name of Party Responsible for Plugging Fees: Woolsey Operating Company  
State of Kansas County, Barber, ss. \_\_\_\_\_  
John Swinford (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John Swinford  
(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 26 day of September, 20 07  
Glenda Morrison My Commission Expires: 11/30/10  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT