

15-101-2181600-00

CONFIDENTIAL

ORIGINAL

CARMEN SCHMITT INC.

P.O. BOX 47

GREAT BEND KS 67530

New Wealth Comes From the Land
620-793-5100

KCC

SEP 02 2003

DRILLING PROGRESS REPORT

CONFIDENTIAL

BENTLEY #1

T16S-R28W, SEC 13: W/2 NW LANE COUNTY KANSAS

ELEVATION: 2694' G.L. 2699' K.B.

COMPARISON WELL FOR EST DEPTH: NW SW SE 13-16S-28W (Slawson's BL Miller)

<u>FORMATION</u>	<u>EST DEPTH</u>	<u>DRILLER DEPTH</u>	<u>LOG DEPTH</u>
ANHYDRITE	2102 (+ 597)	2099 (+ 600)	
TOPEKA	3650 (- 951)	3644 (- 945)	
HEEBNER SHALE	3891 (-1192)	3885 (-1186)	
LANSING	3928 (-1229)	3924 (-1225)	
BASE/ K.C.	4256 (-1557)		
MARMATON	4280 (-1581)		
PAWNEE	4390 (-1691)		
FT. SCOTT	4442 (-1743)		
CHEROKEE	4465 (-1766)		
MISSISSIPPIAN	4568 (-1869)		
TOTAL DEPTH	4631 (-1932)		

RELEASED
FROM
CONFIDENTIAL

- 8-19-03 Pickrell Drilling Company Rig 10 spud at 5:15 p.m. Drilled 12.25" hole to 226'. Hole deviation .75 degree. Ran 5 jts new 23# 8.625" surface casing set at 220' with 160 sx 70/30 poz, 2% gel, 3% c.c. Plug down at 11:40 p.m.
- 8-20-03 at 7:00 a.m. waiting on cement.
- 8-21-03 At 7:00 a.m. drilling at 2020'. Hole deviation at 739' = 1 degree, at 1269' = 1.25 degrees, at 1754' = 1 degree. Drilled Anhydrite 2099'-2132'.
- 8-22-03 At 7:00 a.m. drilling at 2865'. Hole deviation at 2264' = 0.75 degree. At 3:30 p.m. lost circulation at 3089'. Regained circulation and drilled to 3103' where lost circulation again. Drill pipe stuck.
- 8-23-03 At 12:30 a.m. spotted 40 barrels tank bottoms, pulled pipe loose and resumed drilling at 2:15 a.m. At 7:00 a.m. drilling at 3235'.
- 8-24-03 At 7:00 a.m. testing at 4000'. Pipe strap 0.48' long the board. Hole deviation at 4000' = 0.75 degree. DST #1 3969'-4000' 15-30-45-60 Recovery: 10' clean oil, 90' oil cut water (30% oil, 70% water) 495' oil cut water (10% oil, 90% water), 805' slightly oil cut water (3% oil, 97% water). Flow pressures: 64-299/308-695. Shut-in pressures: 1090-1092. Will drill about 115' to "H" zone and test if carries shows.

CONFIDENTIAL

ORIGINAL

KCC

SEP 12 2003

CONFIDENTIAL

FAX REPORT TO:

PAUL SIMPSON	785 625 5620
KYKON OIL & GAS, INC.	406 248 3792
CHARLES E. STEVENS JR. TRUST #1	785 825 5188
RPX ENERGY COMPANY	970 206 1840
STEVE AND KAREN DRAKE	620 662 4497
CURTIS AND KATHLEEN HITSCHMANN	620 653 7332
NEWMAN FARM ENTERPRISES	785 625 8787
MILLER CONSULTING SERVICES	303 623 5062