

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

15-163-02998-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 13-14

LOCATION CS $\frac{1}{2}$ SW $\frac{1}{4}$

SEC. 35 TWP. 8 RGE. 19

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Slansky

Operator Don. K. Wells Address 810 Cent Bldg Wichita, Kans

Field _____ County Rooks

Total Depth 3440 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 180' circulated with cement - 5 1/2" at 3427' with 100
sax cement behind - Lane Wells Plugs to 3130', perforated at
3108'.

Filled with sand to 3085', set 6 sax cement with dump bailer,
pulled 2720' 5 1/2" - pumped hole full commercial mud (30 sax Gel)
pumped cementing plug to 185' followed by 60 sax cement - cement
185' to 0'.

Mudding and Cementing by Globe Cementing Co

Edward Leets
District Conservation Agent

Date 11-6-55

PLUGGING
FILE SEC 35 T 8 R 19 W
BOOK PAGE 13 LINE 14

11-8-55