

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-03188-00-00

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

FEB 11 1963
2-11-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Glickman Oil Co
Complete Address: 702 S St Francis Wichita, Kans
Lease Name Slansky Well No. A-1
Location CS $\frac{1}{2}$ SE SW Sec. 35 Twp. 8 Rge. (E) (W) 19
County Rooks Total Depth 3420
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: same & Halliburton Co
Address: License No.
Operation Completed: Hour 6PM Day 31 Month 1 Year 63

The Above well was plugged as follows:

8 5/8" 130' circulated with cement - 4 $\frac{1}{2}$ " 3404' with 125 sax cement - perf
in Anhydrite and squeezed with cement - no pipe recovery - tubing packer
lost in hole at 3290' with 200' of 2" tubing on top packer.

Pumped hole full heavy gel mud (20 sax Gel) at 1000# pump pressure, followed
mud with 60 sax cement, 500# pump pressure on completion.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/11/63

INV. NO. 6552-W

Signed: [Signature]
Well Plugging Supervisor