

15-163-03189-00-00

CP-3

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENCY

RECEIVED  
STATE CORPORATION COMMISSION

AUG 7 1962  
8-7-62  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Glickman Oil Co  
Complete Address: 702 S St Francis Wichita, Kansas  
Lease Name Slansky Well No. 1  
Location SW SW SE Sec. 35 Twp. 8 Rge. (E) (W) 19  
County Rooks Total Depth 3439  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Barnes & Sons  
Address: Russell, Kansas License No. 9  
Operation Completed: Hour 3PM Day 5 Month 8 Year 62

The Above well was plugged as follows:

8 5/8" 130' circulated with cement - 5 1/2" 3434' with 125 sax cement.

Baker plug at 3411' - perforated 3185'.

Plugged back with sand to 3170', set 4 sax cement with dump bailer,  
pulled 2677' 5 1/2" to 350', circulated hole with heavy gel mud through  
5 1/2" ( 45 sax Gel), displaced 20 sax cement through 5 1/2" at 350', heavy  
mud to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to  
35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 8/3/62  
INV. NO. 5495-a

Signed: Edon Hestey  
Well Plugging Supervisor