

15-163-20520-00-00
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
4/15/74 APR 15 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name J. B. Collins
Complete Address Box 393, Plainville, Kansas
Lease Name Hamel Well No. 1
Location SW SW SE Sec. 6 Twp. 8 Rge. (E) (W) 20
County Rooks Total Depth 3505'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Red Tiger Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 6 P Day 8 Month 4 Year 1974

The above well was plugged as follows:

RTD 3505' 8 5/8 csg set at 200' cwc Cem. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 215' set cementing plug and displaced 20 sk cem.
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/15/74
INV. NO. 8926-U

Signed: Leo P. Massey
Well Plugging Supervisor