

15-163-00573-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 4-51 County: Books

Location: SW SW SW Sec. 12 Twp. 8 Rge. 20 (E) (W)

Name of Field: _____ Total Depth: 5477

I have this date completed supervision of plugging of:

Lease Name: Gosselin Well No. 1

Operator's Full Name: Morganstern & Specter

Complete Address: Box 661 Russell, Kans

Plugging Contractor: E & L Pipe Pulling Co

Address: Great Bend, Kans License No. 377

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 7 Month 1 Year 59

The above well was plugged as follows:

8 5/8" at 118' circulated with cement - 5 1/2" 5477' with 100 sax cement.

P.B. to 5220', perf 5204'.

Filled with sand to 5150', set 4 sax cement with dump bailer, pulled

2750', 5 1/2" to 500', circulated hole with heavy mud through 5 1/2" at 500',

(22 sax Gel), displaced 20 sax cement through 5 1/2" at 500', heavy mud to

180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to 50',

set rock and 10 sax cement to 0'.

Mudding and cementing by E & L Co's pump truck.

Signed: *Edwin Lacey*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 12 T. 8 R. 20W
BOOK PAGE 4 LINE 31

RECEIVED
STATE CORPORATION COMMISSION
1-17-59
JAN 17 1959
CONSERVATION DIVISION
Wichita, Kansas