

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20598-00-00

FEB 19 1976
2-19-76
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Zenith Drlg. Corp., Inc.

Complete Address Suite 600, 200 W. Douglas, Wichita, Kansas

Lease Name Roy Well No. 1

Location SW NW NW Sec. 13 Twp. 8 Rge. (E) (W) 20

County Rooks Total Depth 3507'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 8:45 P Day 17 Month 2 Year 1976

The above well was plugged as follows:

RTD 3507' 8 5/8 csg set 190' cwc 150 sk. Cmt. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-25-76

Signed: Leo J. Massey
Well Plugging Supervisor

INV. NO. 2791-W