

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

15-163-20285-00-01

API Number 15 - 163 - 20,285 - 4 (for this well)

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1978
5-17-78
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Development Co.
Complete Address 300 W. Douglas, Suite ⁶³⁵ 365, Wichita, Kansas
Lease Name Balthazor (OWWO) Well No. 1
Location NW NW SE Sec. 22 Twp. 8 Rge. (E) (W) 20
County Rooks Total Depth 1579'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated Lost Hole
Plugging Contractor Duke Drlg.
Address Great Bend, Kansas License No.
Operation Completed: Hour 6P Day 12 Month 5 Year 1978

The above well was plugged as follows:

RTD 1579' 8 5/8 csg. set 217' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-17-78

INV. NO. 7320-W

Signed: Leo Marney
Well Plugging Supervisor