

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rooks County Sec. 28 Twp. 8 Rge. 19 E/W
Location as "NE/CNW/SW" or footage from lines

C SE NW

Lease Owner Jay Engery Development Corporation

Lease Name Veverka "B" Well No. 1

Office Address 124 S Main, Box 1097 Hesston, KS 67062

Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed March 29 19 81

Application for plugging filed March 29 19 81

Application for plugging approved March 29 19 81

Plugging commenced 1:30 A.M. March 29 1981

Plugging completed 3:00 A.M. March 29 19 81

Reason for abandonment of well or producing formation
no Commercial Production

If a producing well is abandoned, date of last production
19


Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation Depth to top Bottom Tl. Depth of Well

Show depth and thickness of all water, oil and gas formations.

locate well correctly
on above
Section Plot



OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface Casing	common	0'	247.94'	8 5/8"	247.94'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug #1 65 sxs @ 740'

Plug #2 30 sxs @ 270'

Plug #3 10 sxs @ 40'

5 sxs in Rathole

Total 110 sxs 50-50 poz 6% gel Plug Down @ 3:00 A.M.

RECEIVED
STATE CORPORATION COMMISSION

APR 10 1981
4/10/81
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pioneer Drilling Company, Inc.
308 West Mill Plainville, KS 67663

STATE OF Kansas COUNTY OF Harvey, ss.

Arlan R. Yoder

(employee of owner) or (owner or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well is filed and that the same are true and correct. So help me God.


(Signature)

(Address)

Box 1097, Hesston, KS 67062

SUBSCRIBED AND SWORN TO before me this 9 day of April, 1981

My commission expires



Janis M. McCreary
Notary Public

15-163-21228-00-00

15
WELL LOG

OPERATOR: Jay Energy Development Corporation

WELL NAME: Veverka "B" #1 LOCATION: C SE NW 28-8s-19W

COUNTY: Rooks STATE: Kansas

WELL COMMENCED: March 20 1981 WELL COMPLETED: March 29, 1981

ELEVATION: 2048' G.L. TOTAL DEPTH: 3530'

PRODUCTION: D & A RIG NO: #2

CASING - 8 5/8": 247.94' of used 28# cemented with 110 sxs common 2% gel 3% cc did circ
5 1/2": _____

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	824'	sand and shale		
824'	1493'	sand and shale		
1493'	1528'	Anhydrite		
1528'	1753'	shale		
1753'	1970'	sand and shale		
1970'	2323'	lime and shale		
2323'	2480'	shale and lime		
2480'	2538'	shale and lime		
2538'	2565'			
2565'	2577'	shale and lime		
2577'	2647'	shale and lime		
2647'	2655'	shale and lime	2655' - 3 1/2 - degree	RECEIVED STATE CORPORATION COMMISSION
2655'	2755'	lime and shale		
2755'	2873'	lime and shale		
2873'	2973'	lime and shale		
2973'	3080'	lime and shale	3076' - 2 - degree	CONSERVATION DIVISION Wichita, Kansas
3080'	3182'	lime and shale		
3182'	3208'	lime and shale	3208' -1 3/4 - degree	
3208'	3283'	lime and shale		
3283'	3345'	lime and shale		
3345'	3408'	lime and shale		
3408'	3496'	lime and shale		
3496'	3510'	Arbuckle		
3510'	3530'			
3530'	RTD			

RECEIVED
STATE CORPORATION COMMISSION
APR 10 1981
CONSERVATION DIVISION
Wichita, Kansas
4/10/81

STATE OF KANSAS
COUNTY OF _____

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct

PIONEER DRILLING CO., INC.

By Connie Austin

SUBSCRIBED AND SWORN TO, BEFORE ME, This 1st day of April, 1981

Judy Smith
NOTARY PUBLIC

