

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-163-00923-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Rooks County, Sec. 30 Twp. 8 Rge. 19W(E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner Wilkinson-Seneca-Leben

Lease Name Lowrey Well No. 1

Office Address 905 Central Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-26-59 19

Application for plugging filed 12-26-59 19

Application for plugging approved 12-26-59 19


Plugging commenced 12-26-59 19

Plugging completed 12-26-59 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3500 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	237'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug set @ 600' w/ 20 sacks cement.
2nd plug set @ 180' w/ 15 sacks cement.
Top plug set @ 40' w/ 10 sacks cement.

RECORDED
STATE CORPORATION COMMISSION

JAN 5 1960
01-05-1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Frank Hamlin

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Frank Hamlin

905 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of December 19 59

My commission expires April 23, 1963

Juanita M. Green
Notary Public.



15-163-00923-00-00

DRILLER'S LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

COMMENCED:
COMPLETED:

WILKINSON-SENECA-LEBEN
LEBEN DRILLING, INC.
LOWREY #1
SW SW NE SEC. 30-8-19W
ROOKS COUNTY, KANSAS
12-18-59
12-26-59

0	236	Blue Shale
236	335	Shale
335	1000	Shale and Sand
1000	1335	Shale and Redbed
1335	1805	Shale and Shells
1805	1923	Shale and Shells
1923	1983	Anhydrite
1983	2045	Shale and Lime
2045	2175	Lime
2175	2375	Lime and Shale
2375	2510	Lime
2510	2650	Lime
2650	2785	Lime and Shale
2785	2965	Lime and Shale
2965	3035	Lime and Shale
3035	3165	Lime
3165	3225	Lime
3225	3261	Lime
3261	3320	Lime
3320	3360	Lime
3360	3426	Lime
3426	3445	Lime
3445	3493	Lime
3493	3500	Lime
	<u>3500</u>	<u>Rotary Total Depth - D & A</u>

RECEIVED
STATE CORPORATION COMMISSION
JAN 5 1960
CONSERVATION DIVISION
Wichita, Kansas

Set 8 5/8" surface casing @ 237' with 150 sacks of 6 hr. Sunset cement.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Lowrey #1, located SW SW NE of Section 30, Township 8 South, Range 19 West, Rooks County, Kansas, as reflected by the files of Leben Drilling, Inc.

Frank Hamlin
Frank Hamlin

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss.

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 30th day of December, 1959

Juanita M. Green
Juanita M. Green, Notary Public

My Commission Expires:
April 23, 1963