


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks _____ County, Sec. 31 Twp. 8 Rge. 19 (E) _____ (W) ^x

Location as "NE/CNW/SW" or footage from lines SE NW NW
Lease Owner Okmar Oil Co.
Lease Name Hayden Well No. #1
Office Address 1130 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 7-23-65 _____ 19____
Plugging completed 7-27-65 _____ 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3513' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made plug back with sand to 3500', mixed and ran 4 sacks cement thru dump bailer.
Circulated hole with 10 sacks gel and spotted 20 sacks cement at 550'. Pulled 10 joints.
Spotted 20 sacks cement at 200', both thru 5 1/2" casing. Pulled 7 joints.
Mudded back to 40', set 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
AUG 2 - 1965
CONSERVATION DIVISION
Wichita, Kansas
8/2/65

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31 day of July, 1965

My commission expires 24 October 1968
Sidney D. Miller
Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 Wichita, Kansas

15-163-00229-00-00


Company - HEATHMAN-HONAKER DRLG. CO.
 Farm - Hayden No. 1

SEC. 31 T. 8S R. 19W
 NE NE SE

Total Depth. 3517
 Comm. 11-30-48 Comp. 12-10-48
 Shot or Treated. 2000 gals acid
 Contractor. Heathman-Honaker
 Issued. 12-17-49

County. Rooks

KANSAS



CASING:
 8" set @ 219' w/125 sx.
 5" set @ 3513 $\frac{1}{2}$ ' w/150 sx.

Elevation. _____

Production. 122 Bbls.

Figures Indicate Bottom of Formations.

Sand shale	210
Shale	339
Shale & shells	1202
Shale, shells, sand	1535
Anhydrite	1569
Shale shells	2055
Shale lime	2678
Shale	2920
Shale lime	3259
Lime	3408
Shale & lime	3516

RECEIVED
 STATE CORPORATION COMMISSION

JUL 20 1965

CONSERVATION DIVISION
 Wichita, Kansas

7/20/65

Rotary Total Depth

Cable Tools:

Lime 3517

Total Depth

FORMATION TOPS

Anhydrite	1535
Heebner	3227
Lansing	3267
Arbuckle	3513

1000 gal. acid. Perf. (12) 3513 $\frac{1}{2}$ -3516; 1000 gal. acid.