


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-163-00478-00-00
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County. Sec. 31 Twp. 8 Rge. (E) 19 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NE SW
Lease Owner Westgate-Greenland Oil Company
Lease Name C. C. Lowry Well No. 1
Office Address 1009 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed March 2, 1952 19
Application for plugging filed (orally) March 2, 1952 19
Application for plugging approved @ March 2, 1952 19
Plugging commenced March 2, 1952 19
Plugging completed March 2, 1952 6:30 P.M. 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
surface		0	180	8 5/8@	180	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3565(RB) to 170 feet
Set plug at 170 feet and ran 15 sacks cement to 130 feet
Filled hole with heavy mud from 130 feet to 40 feet
Set plug at 40 feet and ran 10 sacks cement to cellar.

2/5/52

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jackson Drilling Corporation
Address 1009 Central Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. E. Bitler (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler
1009 Central Building, Wichita, Ks
(Address)


SUBSCRIBED AND SWORN to before me this 4th day of March 1952

Esther Unsell

Notary Public.

My commission expires May 25, 1953.

23-8390-s 6-51-20M



DRILLERS LOG

COMPANY: Westgate-Greenland Oil Co
 CONTRACTOR: Jackson Drilling Corporation
 FARM Lowry #1 (C.C.)
 LOCATION: SW NE SW Sec 31-8-19W,
 Rooks County, Kansas
 COMMENCED: February 22, 1952
 COMPLETED: March 2, 1952
 ELEVATION: 2045 DF

0	to	70	Soil and shale
70	to	160	Sand and shale
160	to	560	Shale and shells
560	to	695	Sand
695	to	1040	Shale and shells
1040	to	1270	Sand
1270	to	1550	Shale and red bed
1550	to	1585	Anhydrite
1585	to	1900	Shale and shells
1900	to	1990	Shale and lime
1990	to	2090	Lime
2090	to	2275	Shale and shells
2275	to	2325	Shale and lime
2325	to	2380	Lime
2380	to	2410	Lime and shale
2410	to	2415	Lime
2415	to	2545	Shale and shells
2545	to	2705	Lime and shale
2705	to	2850	Shale
2850	to	3267	Lime and shale
3267	to	3490	Lime
3490	to	3535	Lime and shale
3535	to	3565	Arbuckle
		3565	T. D. RB

Set 180 feet of 8 5/8" O.D. 24# surface pipe. Cemented with 125 sacks cement and 2 sacks calcium chloride

TOPS: Anhydrite 1550. Dodge 3254 Base Kansas City 3488
 Heebner 3233 Kansas City 3275 Arbuckle 3534

Dry, plugged and abandoned
 no Schlumberger run

C E R T I F I C A T E

I, Don Allen, do hereby certify that the above and foregoing is a true and correct copy of log of the C. C. Lowry #1 well, Section 31-8-19W, Rooks County, Kansas, as reflected by of the Westgate-Greenland Oil Company.

Don Allen
 Don Allen

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 4th day of March, 1952.

Esther Unsell
 Esther Unsell, Notary Public

My commission expires May 25, 1953.

31 8 1952
 149