


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD Strike out upper line when reporting plugging of formations.

Rooks County. Sec. 31 Twp. 8S Rge. (E) 19W (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ SE $\frac{1}{4}$ SE $\frac{1}{4}$
Lease Owner Heathman-Honaker Drilling Co., Inc., et al
Lease Name Hayden Well No. 2
Office Address 509-510 Orpheum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 2-5-19 49
Application for plugging filed 2-5-19 49
Application for plugging approved 2-5-19 49
Plugging commenced 5:30 A.M. 2-5-19 49
Plugging completed 2-5-49 19 49
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C.D. Stough, Box 207, Great Bend, Kansas
Producing formation none Depth to top Bottom Total Depth of Well 3581 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
none				10-3/4" surface (8 jts.) cemented @ 154' w/ 100 sacks.		none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/heavy mud to 154' cemented bottom hole plug w/20 sacks cement. Hole filled w/heavy mud to within 20' of top of hole; top hole plug cemented with 10 sacks. Surface pipe cut off 2 1/2' below level of ground.

RECORDED
FEB 10 1949
STATE CORPORATION COMMISSION
KANSAS

2/10/49

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Heathman-Honaker Drilling Co., Inc.
Address 509-510 Orpheum Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
H. D. Shreve (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. D. Shreve*
509-510 Orpheum Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of February, 19 49

My commission expires June 28, 1952. *D. M. Maguire* Notary Public.

PLUGGING
FILE SEC 31 T 8 R 19w
BOOK PAGE 82 LINE 10

15-163-02492-00-00

HAYDEN # 2 WELL

Location: Approx. Ctr. SW/4 SE/4 SE/4 Sec. 31-08-19W Rooks County, Kansas Date Spudded: 1-22-49

Operator: Heathman-Honaker Drilling Co., Inc. Rotary Completion Date: 2-5-49

Contractor: Heathman-Honaker Drilling Co., Inc. Total Depth: 3581'

Surface Casing: 8 jts. 10-3/4" 8 thd. cemented @ 15lb w/100 sacks cement. Cement circulated. Elevation: 2073 Ground
2075 Derrick
2077 Kelly Bushing

Oil String: none run
Dry and abandoned: 2-5-49

	<u>T O P S</u>	(Sample)
Anhydrite	1538	
Heebner	3252	
Lansing	3292	(-1215 KB)
Conglomerate	3536	(-1459 KB)
Arbuckle	3551	(-1474 KB)
	No shows	
Total Depth	3581	

L O G
(Figures indicate bottom of formation)

Sand shale	0 to 165'
Shale and sand	835
Shale shells	1538
Anhydrite	1572
Shale and shells	1845
Shale lime	2090
Lime	2111
Shale and lime	2200
Lime and shale	2665
Shale and lime	2715
Lime and shale	2983
Shale and lime	3058
Lime and shale	3392
Lime	3413
Lime and shale	3538
Lime and sand	3542
Lime and chert	3557
Cherty Lime	3581
Total Depth	3581'

RECEIVED
FEB 10 1949
STATE CORPORATION COMMISSION
TULSA, OKLA.

2/10/49

The undersigned, H. D. Shreve, of the Heathman-Honaker Drilling Co., Inc., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

HEATHMAN-HONAKER DRILLING CO., INC.

BY: H. D. Shreve
H. D. Shreve

Subscribed and sworn to before me
this 9th day of February, 1949.

My commission expires: June 28, 1952.

D. Marjorie Matt
Notary Public

PLUGGING
FILE SEC 31 T 8 R 19 W
BOOK PAGE 82 LINE 10