

15-163-21391-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY ROOKS SEC. 31 TWP. 8 RGE. 19W X/W  
Location as in quarters or footage from lines:  
2310' FNL & 990' FEL NE/4

2310'				
FNL			X	

990' FEL

Locate Well  
correctly on above  
Section Platt.

Lease Owner TXO Production Corp.  
Lease Name Atwood A #1 Well No. 1  
Office Address 200 W. Douglas, Suite 300, Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry hole  
Date Well Completed September 9, 1981  
Application for plugging filed September 8, 1981, verbally  
Plugging commenced 10:00 a.m. September 9, 1981  
Plugging completed 12:45 p.m. September 9, 1981  
Reason for abandonment of well or producing formation Oil insufficient to economically produce.  
Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation N/A Depth to top N/A bottom N/A T.D. N/A  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8" 201b	247'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. Plugged with 50-50 pozmix - 6% gel.

- Set 1st Plug @ 860' with 60 sacks
- Set 2nd Plug @ 240' with 40 sacks
- Set 3rd Plug @ 40' with 10 sacks
- 5 sacks rathole
- 5 sacks mousehole

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 23 1981 9/23/81  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Allied Cementing Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
C. K. Morrison (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. K. Morrison  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of September, 1981

Suzanne P. Graef  
Suzanne P. Graef Notary Public.

My Commission expires: October 26, 1981



15-163-21391-00-00

September 18, 1981

CONTRACTOR'S WELL LOG

OPERATOR: TXO Production Corporation  
 CONTRACTOR: KANDRILCO, Ltd.  
 WELL NAME: Atwood A #1  
 LOCATION: 2310' FNL, 990' FEL NE/4 of Sec. 31, T8S-R19W, Rooks County, KS  
 API NO.: 15-163-21,391  
 COMMENCED: August 28, 1981  
 COMPLETED: September 9, 1981

Drilled 267' of 12 1/4" hole. Set 247' of new 8 5/8" 20# casing at 247' with 150 sacks light - 3% CaCl, 2% gel and 100 sacks of common cement - 2% gel, 3% CaCl. Cement did circulate to surface. Plug was down at 12:00 a.m., August 29, 1981.

<u>FORMATION</u>	<u>TOP'</u>	<u>BOTTOM'</u>
Sand and Shells	0	267
Shells & Shale	267	1400
Shells, Shale and Lime	1400	2150
Shale and Lime	2150	3150
Lime, Shale & Chert	3150	3400
Lime and Chert	3400	3570

RTD 3570'. Plugged to abandon. Plugged with 50-50 Pozmix, 6% gel. Set 60 sacks at 850', 40 sacks at 240', 10 sacks at 40', 5 sacks rathole and 5 sacks mousehole. Plugging complete at 12:45 p.m., September 9, 1981.

STATE OF KANSAS, COUNTY OF SEDGWICK, SS:


I, C. K. Morrison, President, KANDRILCO, Ltd., do hereby state that the above is a true and correct copy of the Driller's Log for the TXO Production Corp. Atwood A #1 located in Rooks County, Kansas.

KANDRILCO, Ltd.

*C. K. Morrison*  
C. K. Morrison, President

RECEIVED  
STATE CORPORATION COMMISSION  
7 27 1981  
CONSERVATION DIVISION  
Wichita, Kansas  
9/23/81

Subscribed and sworn to before me, a Notary Public, in and for the County and State aforesaid, as of this 18th day of September, 1981.



*Suzanne P. Graef*  
Suzanne P. Graef - Notary Public

My Commission expires: October 26, 1981