

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-22,887 0000

LEASE NAME McClellan

WELL NUMBER #1

330' Ft. from S Section Line

2310' Ft. from E Section Line

SEC. 31 TWP. 8 RGE. 19 (X) or (W)

COUNTY Rooks

Date Well Completed 8/27/86

Plugging Commenced 8/27/86

Plugging Completed 8/27/86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Lee Phillips Oil Company

ADDRESS 125 N. Market, Suite 1532, Wichita, Kansas 67202

PHONE# (316) 264-6392 OPERATORS LICENSE NO. 5215

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	287'	8 5/8"	287'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Plugged hole w/200 sx 60/40 poz, 4% gel, 3% cc as follows:  
25 sx @ 1600', 100 sx @ 900' plus 1 sk Flocele, 40 sx @ 320', 10 sx @ 40' with wiper plug,  
10 sx M.H., 15 sx R.H. P.D. at 6:00 p.m. 8/27/86

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard J V, INC. License No. 4958

Address P. O. Box 905 McPherson, Kansas 67460

STATE OF Kansas COUNTY OF Sedgewick, ss.

Lee E. Phillips III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

**RECEIVED**  
STATE CORPORATION COMMISSION  
CONS. DIV. WICHITA, KS

(Signature) Lee E. Phillips III

(Address) 125 N. Market Suite 1532

SUBSCRIBED AND SWORN TO before me this 28 day of August, 19 86

Alice M. Oaks  
Notary Public

**RECEIVED**  
STATE CORPORATION COMMISSION  
CONS. DIV. WICHITA, KS

My Commission Expires: \_\_\_\_\_

**ALICE M. OAKS**  
State of Kansas  
My Appt. Exp. May 10, 1988

Form CP-4  
Revised 08-84

OCT 2, 1986

DRILLERS' LOG

COMPANY: Lee Phillips Oil Company
125 N. Market Suite 1532
Wichita, Kansas 67202
CONTRACTOR: Mallard Drilling
P. O. Box 905
McPherson, KS 67460
COMMENCED: August 21, 1986
COMPLETED: August 27, 1986
TOTAL DEPTH: 3575'

WELL: McClellan #1
API#: 15-163-22,887-0000
LOCATION: SW SW SE
Sec. 31, Twp. 8, Rge. 19W
COUNTY: Rooks County, Kansas
ELEVATION: 2052 G.L.
2060 K.B.

\*\*\*\*\*

Table with 3 columns: FORMATION, FROM, TO. Rows include Soil, shale (0-1013), Sand (1013-1260), Shale (1260-1544), Anhydrite (1544-1579), Lime, shale (1579-2146), Shale (2146-3271), Lime (3271-3399), Lansing (3399-3497), Arbuckle (3497-3540), Conglomerate (3540-3575 RTD).

Cut 12 1/4" hole to 286.72' and ran 7 jts 8 5/8" surface casing. Set on bottom w/lid jt. and cemented w/196 sx 60/40 poz, 6% gel, 3%cc. C.D.C. P.D. at 3:00 a.m. 8/21/86.

Ran electric log and 2 DST's.

Plugged hole w/200 sx 60/40 poz, 4% gel, 3% cc as follows:
25 sx @ 1600'
100 sx @ 900' plus 1 sk Flocele
40 sx @ 320'
10 sx @ 40' with wiper plug
10 sx M.H., 15 sx R.H.
P.D. at 6:00 p.m. 8/27/86.


\*\*\*\*\*

STATE OF KANSAS )
) SS:
COUNTY OF McPHERSON)

I, BRYAN HESS of MALLARD DRILLING, do hereby certify that this is a true and correct copy of the log of the McClellan #1 well as reflected by the files of Mallard Drilling.

Bryan Hess
Bryan Hess, Gen. Mgr.

Subscribed and sworn to before me this 5 day of Sept, 1986.



Don J. Reichenberger
Notary Public