


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-443-03417-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County, Sec. 32 Twp. 8 Rge. 19 (E) (W)

Location as "NE/CNW/SW" or footage from lines N $\frac{1}{2}$ - N $\frac{1}{2}$ - SW $\frac{1}{4}$
 Lease Owner Finder Pipe & Supply
 Lease Name Wines Well No. 1
 Office Address Russell, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) _____
 Date well completed _____ 19____
 Application for plugging filed _____ 19____
 Application for plugging approved _____ 19____
 Plugging commenced Oct. 25 1962
 Plugging completed Dec. 6 1962
 Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3515 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3515 feet to surface feet for each plug set.

Pipe set at 3509 sanded up to 3500' dump 5 sacks of cement.
 Pulled pipe up to 600' cir. with mud, pump 22 sacks of mud,
 Pump 20 sacks of cement to 600', Pulled pipe up to 180', pump 20 sacks
 of cement to 180', pulled pipe & put 10 sacks of cement on top.
 Well completed

DEC 20 1962

12/20/62

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.
 Address Russell, Kansas

STATE OF _____, COUNTY OF _____, ss.
 _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glenn L. Hamilton
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of December, 1962

My commission expires May 26, 1963
Ruth Phillips Notary Public.



WELL LOG

15-163-03417 -00-00


COMPANY Grant Oil Company

SEC. 32 T. 8 R. 19
LOC. N/2 N/2 SW/4

FARM WINES NO. One

TOTAL DEPTH 3515'
COMM. 5/20/58 COMP. 5/28/58
SHOT OR TREATED No
CONTRACTOR Murfin Drilling Company - Rig #4
ISSUED

COUNTRY Rocks
KANSAS



CASING
20 10
15 8 5/8" 193' with 160 sacks cement
12 6
13 5 1/2" 3509'

ELEVATION 2064'

PRODUCTION Producer

FIGURES INDICATE BOTTOM OF FORMATIONS

55' Clay
95' Gray Shale
125' Sand Shale
190' Blue Shale-Shells
595' Shale-Shells
710' Sand
1000' Shale-Shells
1240' Sand
1435' Shale w/Sand Streaks
1552' Sand-Red Bed
2010' Shale & Shells
2970' Shale-Lime
3195' Lime & Shale
3410' Lime
3515' Lime & Shale
3515' Rotary Total Depth

TOPS:

Topeka 3024' -960
Hebner 3228' -1164
Toronto 3250' -1186
Kansas City 3268' -1204
Conglomerate None
Arbuckle 3507' -1443
RTD 3515' -1451
Cable Tool 3515'

DST #1 3508'-3515' Open 2 hrs.
Recovered 60' clean oil, 40' muddy
oil, 140' Very heavy oil cut mud,
no water. FBHP 240#

DEC 20 1962

12/20/62

State of Kansas
County of Sedgwick } ss:

I, Fred Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the WINES #1 well.

Fred Murfin

Fred Murfin

Subscribed and sworn to before me this 25th day of October 19 62

My Commission Expires: June 14, 1964

Mary Louise Blume

NOTARY PUBLIC