


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Rooks County, Sec. 35 Twp. 8 Rge. 19 (X) W (W)

Location as "NE/CNW/SW" or footage from lines C - S/2 SE SW  
Lease Owner Glickman Oil Company  
Lease Name Slansky "A" Well No. 1  
Office Address P.O. Box 3104, Washington St. Station, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed March 12 19 51  
Application for plugging filed February 1 19 63  
Application for plugging approved February 1 19 63  
Plugging commenced February 1 19 63  
Plugging completed February 1 19 63  
Reason for abandonment of well or producing formation Making 2 bbls. oil per day.  
And hole in production pipe - Non-profitable to repair  
If a producing well is abandoned, date of last production December 12 19 63  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation Lansing - Kansas City Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3409 Feet  
Show depth and thickness of all water, oil and gas formations. Plug back to 3342 Feet

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	130'	NONE
				4-1/2"	3404'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 0 feet to 750 feet for each plug set.

25 sxs. Mud mixed very heavy and pumped into casing displacing capacity of same. Followed by pumping 60 sxs. cement on top. Final pressure 750#.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 28 1963

CONSERVATION DIVISION  
Wichita, Kansas

2-28-63

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Cementing Company  
Address Hays, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Milton Glickman

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Milton Glickman Partner  
P.O. Box 3104, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of February, 19 63

My commission expires November 19, 1963. Lorella Schauf Notary Public.



WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

COPY


15-163-03188-00-00

Company- STRAIN DRILLING et al  
Farm- Slansky "A" No. 1

SEC. 35 T. 8 R. 19T  
CS/2 SE SW

Total Depth. 3409 RB  
Comm. 3-2-51 Comp. 3-12-51  
Shot or Treated.  
Contractor.  
Issued. 12-1-51

County Rooks  
KANSAS



8 5/8" CASING:  
130' cem w/75 sx.  
4 1/2" 3404' cem w/125 sx.

Elevation. 1963 ft

Production. 104 bbls

Figures Indicate Bottom of Formations.

sand, shale	30
shale	128
shale, shells	730
shale	840
sand	1090
red rock, shale	1365
anhydrite	1405
shale, shells	1930
lime, shells	1975
lime	2090
lime, shells	2200
lime	2425
lime, shale	2630
shale	2785
shale, lime	3005
shale	3034
lime	3050
shells, lime	3105
lime	3405
arbuckle	3409 RB
Total Depth	

Tops:  
Anhydrite 1365  
Heebner 3111  
Kansas ity 3151  
Arbuckle 3402

DST:  
3302-28 open 15 min.  
Rec. 410' mud cut salt  
water BHP 1100 - 15 min.

3404-09 open 30 min.  
Rec. 260' green oil, 60' oil  
gas cut mud BHP 950' - 15 min.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 28 1963  
2-28-63  
CONSERVATION DIVISION  
Wichita, Kansas