

6 080116

7-29-88

065-22,461 -00-00

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE NW, SEC. 10, T. 8 S, R. 22 W/E

TECHNICIAN'S PLUGGING REPORT

2970 feet from S section line

2970 feet from E section line

Operator License # 5011

Lease Name Boyd Well # 1

Operator: Viking Resources

County Graham 114.73

Name & Address 120 S. Market, Suite 518

Well Total Depth 3530 feet

Wichita, Kansas 67202-3819

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 200

Abandoned Oil Well Gas Well Input Well SWD Well D&A XX

Other well as hereinafter indicated

Plugging Contractor Mallard JV, Inc. License Number 4958

Address McPherson, Kansas

Company to plug at: Hour: am Day: 29 Month: 7 Year: 19 88

Plugging proposal received from Wayne Stout

(company name) Mallard JV, Inc. (phone)

were: Order 190 sx 60/40 poz-mix, 6% gel, 3% cal cl., 1 sx flo-cel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

RECEIVED
STATE CORPORATION COMMISSION
8-23-88
AUG 23 1988

Plugging Proposal Received by Bruce D. Basye (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XXX

Operations observed: Hour: 11:00am Day: 29 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT 1st Plug @ 1670' w/ 25 sx

2nd Plug @ 895' w/ 100 sx. 1 sx flo-cel

3rd Plug @ 250' w/ 25 sx.

4th Plug @ 40' w/ 10 sx

15 sx in rat hole, 15 sx in mouse hole.

Remarks: (If additional description is necessary, use BACK of this form.)

I (XXX) did not observe this plugging.

DATE 8-24-88

Signed Bruce D. Basye (TECHNICIAN)

Bruce D. Basye

NOV 12 1988 SEP 12 1988