

MAR 16 1987

6 030859

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-22,359-00-00
NWSE NW SEC. 19, T 8 S, R 22 W

3630 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5538

Lease Name QUINT Well # B-3

Operator: TOMKAT LTD.

County GRANHAM 117.16

Name & Address P.O. Box 20413

Well Total Depth 3605' feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67208

Surface Casing: Size 8 5/8" feet 259'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor LOBO DRLG. CO. License Number 5864

Address WICHITA, KANSAS

Company to plug at: Hour: PM Day: 16 Month: 3 Year: 19 87

Plugging proposal received from ERVIN NEIGHBORS

(company name) LOBO DRLG (phone) _____

were: 8 5/8" SET @ 259' w/ 150SX. CWC. CIRCULATE HOLE w/ NO LESS THAN 36 UIS.
MUD. MAINTAIN FLUID LEVEL @ SURFACE w/ NO LOSS OR GAIN OF FLUID
SPOT CMT. PLUGS w/ DRILL P. PE & BALANCE PLUGS w/ MUD. ORDER
190 SX. 60/40 POZ 6% GEL 3% CC 8 5/8 W.P. ALLIED CMT. CO.

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3: PM Day: 16 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT SPOT D.P. @ 1775' DISPLACE 25 SX. CMT. MIX LAY DOWN D.P.
TO 850' DISPLACE 100 SX. 60/40 POZ 6% GEL 3% CC w/ 1 SX. HULLS LAY DOWN D.P.
TO 300' DISPLACE 40 SX. CMT. MIX LAY DOWN D.P. ADJUST MUD IN
HOLE TO 40' OR KELLY DEPTH PUSH W.P. TO KELLY DEPTH, FILL HOLE TO
BASE OF CELLAR WITH 10 SX. CMT. MIX. CIRCULATE 15 SX. CMT MIX IN RATHOLE
w/ JOINT OF PIPE TO PLOW DEPTH. PLUG COMPLETE.

Remarks: ELEV. 2135' ANHY 1775'
(If additional description is necessary, use BACK of this form.)

INVOICED (I did not observe this plugging.)

RECEIVED
STATE CORPORATION COMMISSION
APR 20 1987
CONSERVATION DIVISION
Wichita, Kansas
Carl Goodnow
(TECHNICIAN)

DATE 4-21-87

INV. NO. 16599