

6 070552

APR 16 1987

239 R

API NUMBER 15- 065-22-365-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NW NE NW SEC. 19, T 8 S, R 22 W 1/2 W

TECHNICIAN'S PLUGGING REPORT

4950 feet from S section line

3630 feet from E section line

Operator License # 6129

Lease Name Quint Well # C #3

Operator: Jay C. Boyer

County Graham 119.81

Name & Address P.O. Box 511

Well Total Depth 3625 feet

Hays, Kansas 67601

Conductor Pipe: Size 0 feet

Jay C. Boyer

Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Western Kansas Drilling Inc. License Number 4083

Address Hays, Kansas 67601

Company to plug at: Hour: 10:00 P.M. Day: 16th Month: April Year: 19 87

Plugging proposal received from Frank Taggert

(company name) Western Kansas Drilling Inc. (phone) 913-625-6967

were: 8 5/8" 208 Ft. S. P. CWC w/135 sk 60/40 Pozmix 3 % Gel 2% Ca CL. By B. J. Titan

Proposal 190 sk 60/40 Pozmix 6 % Gel 3% Ca Cl., 1 sk Cello Flake, and 8 5/8" Plug.

Spot with drill stem, recondition hole, heavy mud between all plugs. Elev. 2129', Any

1752' No circulation problems, mud 47 Vis 9.8 weight. 25 sk @ 1770', 100 sk @ 950'

with Cello Flake, 40 sk @ 250', 10 sk @ 40', 15 sk Rat Hole. (42 to 45 Vis Mud)

Plugging Proposal Received by Mervin Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 P.M. Day: 16 Month: April Year: 19 87

ACTUAL PLUGGING REPORT Ordered 190 sk 60/40 Pozmix 6% Gel, 3% Ca. Cl. 1 sk Cello Flake.

Spot with drill stem reconditioned hole, heavy mud between all plugs.

1st plug @ 1770 ft w/25 sk cmt; 2nd plug @ 950 ft. w/100 sk cmt. w/1 sk Cello Flake.

3rd, plug @ 250 ft. w/40 sk cmt; 4th plug half sx. Hulls wiper plug @ 40 ft. w/10 sk cmt.

15 sk. cement in rat hole (circulate)

Cemented by B. J. Titan

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

May 4, 1987

INVOICED

If additional description is necessary, use BACK MAT this form.

I (did / did not) observe this plugging.

DATE 5-6-87 Jr DB-mms

Signed Mervin Schmidt  
(TECHNICIAN)

INV. NO. 16776

Witnessed by - Carl Goodnow

4-16 MAY 27 1987