

6020176

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,083 -00-00

SW SW NW, SEC. 30, T 8 S, R 22 W 22
2970 feet from ~~XXX~~ SE section line
4950 feet from ~~XXX~~ SE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428
Operator: Graves Drilling Co.
Name & Address: 910 Union Center
Wichita, Ks. 67202

Lease Name Rice Well # 1
County Graham
Well Total Depth 3705 120.41 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 369

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Big Springs Drilling License Number 5381

Address Wichita, Ks.

Company to plug at: Hour: PM Day: 23 Month: October Year: 19 84

Plugging proposal received from Darrel Kirer

(company name) Big Spring Drilling (phone) _____

were: Order 185 lbs. 50/50 pozmix 6% gel 3% cal. cl., 2 sk flo-cel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 1:45 PM Day: 24 Month: October Year: 19 84

ACTUAL PLUGGING REPORT

- 1st plug @ 1900 w/25 sks
- 2nd plug @ 930 w/100 sks
- 3rd plug @ 380 w/40 sks
- 4th plug @ 40 w/10 sks Bridge
- 10 sks in Rat Hole

Remarks: Cemented by Allied (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-8-84
INV. NO. 4704

Signed Gilbert Balthezas (TECHNICIAN) 11-2-84

STATE CORPORATION COMMISSION
RECEIVED
NOV 05 1984
CONSERVATION DIVISION
Wichita, Kansas