

To: 6030526  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SENE5W, SEC. 32, T. 8 S, R 22 W  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-0165-20518-00-00  
1650 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033  
Operator: MUREIN DRUG. CO.  
Name & Address 250 N. WATER STE 300  
WICHITA, KANSAS  
67202

Lease Name HULL Well # 1  
County GRAHAM 126.75  
Well Total Depth 3900 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 208'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor HALLIBURTON CMT. CO License Number 4

Address OBERLIN, KANSAS

Company to plug at: Hour: PM Day: 25 Month: 7 Year: 19 85

Plugging proposal received from PAT CANADAY

(company name) MUREIN DRUG. (phone) \_\_\_\_\_

were: 8 5/8 SET @ 208' w/ 145 SX. 5 1/2" SET @ 3813' w/ 125 SX. PERF. 3624  
NO PIPE PULLED. ORDER 250 SX. 60/40 PPT. 8% GEL. 3% CC. 20 SX.  
GEL. 4 SX. HULLS. HALLIBURTON CEMENT CO. KELLER WATER TRUCKS

Plugging Proposal Received by Carl Goodlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5: PM Day: 25 Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT PUMP ON BACKSIDE HIT 500# PSI. WOULD NOT TAKE.  
PUMP DOWN 5 1/2" w/ 2 SX. HULLS 50 SX. CMT MIX. 20 SX. GEL. 100 SX. CMT.  
MIX. MAX. PSI 600# CLOSE IN @ 300# PSI. PLUG. COMPLETE.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
08-05-1985  
AUG 5 1985

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED (If you did not observe this plugging.)

DATE AUG 07 1985  
INV. NO. 9402  
7-25

Signed Carl Goodlow 8-2-85  
(TECHNICIAN) mgj