

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21671-00-00  
Spot: CSWNÉSE Sec/Twnshp/Rge: 32-8S-22W  
1650 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: HULL Well Number: 1  
County: GRAHAM Total Vertical Depth: 3865 feet

Operator License No.: 5135  
Op Name: FARMER, JOHN O., INC.  
Address: PO BOX 352 370 W WICHITA AVE  
RUSSELL, KS 67665

Conductor Pipe: Size feet: 8/25.61  
Surface Casing: Size 8.625 feet: 228 155 SX CMT  
Production: Size 5.5 feet: 3854 150 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/04/2002 10:00 AM  
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.  
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-3144

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls - 16 sxs gel.  
Perfs and bridge plug set at 3681' - 3686' and 3854' - 3857'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/04/2002 11:15 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Perf Tech ran hole and perforated at 1850' and 975'.  
Tied onto backside and pumped 40 sxs 60/40 pozmix with Max. P.S.I. 200#. S.I.P. 0#.  
Rigged up on casing and pumped 40 sxs 60/40 pozmix with 300# hulls, followed with 16 sxs gel.  
Pumped an additional 170 sxs with 200# hulls to fill casing.  
Max. P.S.I. 900#. S.I.P. 300#.  
Job complete.

RECEIVED

JUN 13 2002  
06-13-2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY - TICKET #9327.

Plugged through: CSG

District: 04

Signed [Signature]

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 6-13-02

INV. NO. 2002061949

JUN 05 2002

JOHN O. FARMER, INC.

32-8-22W  
SW NE SE

P.O. BOX 352

#1 HULL


RUSSELL, KS. 67665

CONTR JOHN O. FARMER, INC.

CTY GRAHAM

GEOL

FIELD HULL



ELV 2242 K.B. SPD 7/20/82 CARD ISSUED 9/30/82 IP P 20 BOPD & 2% WTR

LANS 3681-3686

API 15-065-21,671

LOG	Tops	Depth Datum
ANH	1824+	418
HER	3456	1214
TOR	3478	1236
LANS	3490	1248
BKC	3708	1466
PAW	3774	1532
CONG	3833	1591
ARB	3846	1604
LTD	3854	1612
RTD	3857	1615

8 5:8 " 228:155SX; 5 1/2 " 3854

DST (1) 3555-3579/15-15, 2'M, ISIP 68#, FSIP NONE, FP 68-68#

DST (2) 3640-3680 / 30-30-10, 10'M, ISIP 78#, FSIP NONE, IFP 78#, FFP NONE

DST (3) 3675-3715 / 45-45-45-45, 372' G, 216' FO, 492' GSMCO, 5'W, SIP 902-824#, FP 118-177 / 265-285#

DST (4) 3790-3850 / 45-45-10, 10' OCM, ISIP 88#, FSIP NONE, FP 59-59#

DST (5) 3850-55 / 45-45-15-30, 50'G, 50' SOCM, SIP 804-697#, FP 68-68 / 78-78#

MICT - CO, PF 3681-86, W / 4 SPF, AC 2000G, SWB LD, R&T, POP, P 20 BOPD & 2% WTR, 9/1/82

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS