

6 030946

9-7-87

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,397 -00-00
SW NW NW, SEC. 35, T 8 S, R 22 (W/EX)
4290 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 06723

Operator: Camio Oil Company
Name & Address: 16046 East Harry
Wichita, Kansas 67230

Lease Name George Buss Well # 1
County Graham 121.55
Well Total Depth 3740 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 317

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Inc. License Number 5422

Address Wichita, Kansas 67202

Company to plug at: Hour: PM Day: 7 Month: Sept Year: 19 87

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling (phone) _____

were: _____

8 5/8" set at 317' w/225 sks. Circ. hole w/no less than 36 vis. mud w/no loss or gain of hole fluid. Displace cement plugs w/drill pipe. Balance all plugs with mud. Order 190 sks/ 60/40 Pozmix 6% Gel 3% Ca C1 cement Blend w/8 5/8" wiper plug. Allied Cement.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:40 PM Day: 7 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT

With drill pipe displace 25 sks at 1775'
100 sks at 950' w/1 sk Hulls
40 sks at 360'
10 sks at 40' w/w.p. to Kelly depth

Circulated to Plow depth. 15 sks in rat hole w/joint of pipe.

Remarks: Anyh 1751' - 86' Elevation 2202'.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 9-28-87

INV. NO. 18277

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow