

S-31

6-100412

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,561-00-00

NW SE NW /4 SEC. 36, 08 S, 22 W
3630 feet from S section line
3560 feet from E section line

Operator license# 4767 Lease DeYoung well # 1

Operator: Ritchie Exploration, Inc. County Graham

Address: 125 North Market Well total depth 3790 feet - 123.17
Suite 1000 Conductor Pipe: inch @ feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 217 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling Company License# 6033

Address: Wichita, Kansas 67202

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Lloyd Dellett

Company: Murfin Drilling phone:

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 3755 feet with 25 sacks Rat hole: 15 sacks
2nd plug @ 1675 feet " 25 " Mousehole: 10 sacks
3rd plug @ 980 feet " 100 "
4th plug @ 260 feet " 40 "

5th plug @ 40 feet " wiper plug & 10 sacks

Plugging Proposal Received by:

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 12:30 am, Day: 31, Month: May, Year: 1990

Actual plugging report: Hole reported plugged as above.

Order 225sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2157 GL, Anhydrite depth: 1668 - 1716 feet

Did penetrate Arbuckle, cemented by Allied

I did not [X] observe the plugging. David K. Wann

David K. Wann P.I.R.T. II
(agent)

Form CP-2/3

STATE CORPORATION COMMISSION
RECEIVED

INVOICED

08-22-1990
CONSERVATION DIVISION
Wichita, Kansas

DATE: 8-28-90
INV. NO. 28141