

6-17 4-031941

065-01325-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1958
NE NE SW /4 SEC. 16 , 08 S, 23 W
2310 feet from S section line
2970 feet from E section line

Operator license# 6332 Lease Bethell well # B-1

Operator: Ken Bill County Graham

Address: 5105 Telstar Street Well total depth 3655 feet
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 160 feet

118.78

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 17 Month: June Year: 94

Plugging proposal received from: Darrell

Company: Kelso Casing Pullers, Inc. Phone:

Were: Order 225 sxs. 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:30P.M., Day: 17, Month: June, Year: 94

Actual plugging report: 8 5/8" set at 160' w/125 sxs. 5 1/2" set at 3654' w/100 sxs. Prod. perf. 3472' - 3486'. PBTD 3500'. Rods and pump stuck in tubing at 2400'. Backed off. Rods and tubing at 2400'. Wireline shots at critical control areas at 1834' and 1030'. Ran tubing in to 2400' - stage cement slurry with hulls. Mixed in to surface - squeezed 5 1/2" casing with total of 110 sxs. cement blend with 500# hulls to Max. P.S.I. 500#. Close in P.S.I. 100#. Squeezed 8 5/8" with 50 sxs. cement blend to Max. P.S.I. 500#. Close in P.S.I. 500#.
Plug complete.

Remarks: Condition of casing(in hole):GOOD BAD X Anhy.plug:YES X NO
Bottom plug(in place):YES , CALC X, NO Dakota plug:YES X, NO
Plugged through TUBING X, CASING . Elevation:

I did X observe the plugging.

INVOICED

JUL 06 1994

DATE

INV. NO. 40758

Carl Goodrow JUN 30 1994

(agent) CONSERVATION DIVISION
Form CP-2/3 Wichita, Kansas

RECEIVED STATE CORPORATION COMMISSION