

6 030443

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065-22,172-00-00  
SWNW SEC. 12, T. 8 S, R 24 (W)  
4050 feet from M/S section line  
4950 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6040  
Operator: Bankoff oil Co.  
Name & Address Box 700657  
Tulsa Oklahoma  
74170

Lease Name Schweitzer Well # 2  
County Graham 124.48  
Well Total Depth 3830 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 200'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger License Number 5302

Address 1720 KSB Bldg. Wichita, Kansas 67202

Company to plug at: Hour: PM Day: 12 Month: 5 Year: 19 85

Plugging proposal received from Kreller

(company name) Red Tiger (phone) \_\_\_\_\_

were: 8 5/8" at @ 200' w/ 1500y. With hole full of no less than 36 vis. mud.  
and no loss or gain of fluid spot cement plugs with 4 1/2" D.P. Order  
1900y 50/50pg 6.4gal 3"oc Pat flo seal 8 5/8" W.P. Allied Cem. Co.  
Water from Pond. Hays tank service.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:30 PM Day: 12 Month: 5 Year: 19 85

ACTUAL PLUGGING REPORT Spot 4 1/2" D.P. @ 2000' displace 250y Cem. mix. laydown  
D.P. to 1150' displace 1000y Cem. mix. + 100y flo seal. laydown D.P.  
to 225' displace 400y Cem. mix. laydown D.P. Push 8 5/8" W.P. To  
Kelly depth and fill hole with Cem. mix. from W.P. to Cellar door 100y.  
displace 150y in Rathole with a joint of pipe. Plug complete.

RECEIVED

Remarks: Elev. 2355 only 1997-2033 log.  
(If additional description is necessary, use BACK of this form.)

MAY 28 1985

(did / did not) observe this plugging.

INVOICED

CONSERVATION DIVISION  
Wichita, Kansas

Signed Carl Goodrow  
(TECHNICIAN)

DATE 5-29-85 5-28-1985

INV. NO. 8281