

4-031931

5-24

API number: 15-065-21,551-0000

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SW SW /4 SEC. 19, 08 S, 24 W  
990 feet from S section line  
4950 feet from E section line

Operator license# 3736 Lease Keith well # 1

Operator: R.L.T. Pfeifer Dozer Service County Graham

Address: St. Peter Route - Box 234 Well total depth 4015 feet  
Morland, Kansas 67650 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 297 feet

130.48

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton License# -

Address: Oberlin, Kansas

Company to plug at: Hour: A.M. Day: 24 Month: May Year: 94

Plugging proposal received from: Leon

Company: R.L.T. Phone: \_\_\_\_\_

Were: Order 170 sxs. 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 12:00P.M., Day: 24, Month: May, Year: 94

Actual plugging report: 8 5/8" set @ 297' w/220 sxs. cwc. 4 1/2" set @ 4014' w/150 sxs. D.V. set @ 2125' w/450 sxs. cwc. Prod. perms. 3893' - 3913'. Set plug above perms. 3366'. Dump 2 sxs. sand on plug - pull tubing to 2500' - spot 40 sxs. cement blend - pull tubing to 1600' - circulated with 80 sxs. cement blend. Pull tubing. Plug complete. Cement in 8 5/8" at surface.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO

Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: \_\_\_\_\_

I did  observe the plugging.

**INVOICED**

DATE 6-16-94

INV. NO. 40577

RECEIVED STATE COMMISSION  
Carl Goodrow

JUN 15 1994  
6-15-94  
Conservation Division  
Wichita, Kansas  
Form CP-2/3