

4-041716

15-163-19358-00-00

API Number: 15-163-01385-00-01 N/A

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SE /4 SEC. 36, 08 S, 17 W  
100 feet from S section line  
430 feet from E section line

Operator license# 8735

Lease: Hrabe Well # 1 SWD

Operator: S &amp; M Oil

County: Rocks

Address: 2730 Thunderbird Dr  
2984 Canal Blvd.  
Hays, Kansas 67601

Well total depth 950 35.00 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 0 feet

Aband. oil well, Gas well, Input well, SWD X, D &amp; A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 13 Month: September Year: 1995

Plugging proposal received from: Steve Crawford

Company: S &amp; M Oil Phone:

Were: 4 1/2" casing set at 980' cwc. Perf. At 915' - 940'. W.L.M. at 930'. Tubing string left in the hole. Pumped down tubing with H2O and flag to determine condition and depth of tubing. Flag circulated to surface ater 10 bbls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 12:00 P.M., Day: 13, Month: September, Year: 1995

Actual plugging report: Pumped - tubing base of hole at 700+. Hooked-up cementers pumped down annulus of tubing (down 4 1/2" casing) and circulated cement to surface out of 2" tubing. Shut in annulus and hooked-up to 2" casing and pumped a total of 75 sxs cement with 100# hulls. Max. P.S.I. 400#. Job completed.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 25 1995

Remarks:

Condition of casing(in hole): GOOD BAD Any plug: YES NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO  
Plugged through TUBING, CASING. Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED

DATE 10-6-95

INV. NO. 43679

9-13 DEC 07 1995