

6 040940

8-10

API NUMBER 15- 163-21,483 0500

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C W/2 NW, SEC. 31, T 8 S, R 17 W/E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5537

Lease Name Dopita Well # A-9

Operator: Kenny Brown Ent

County _____ Rooks 111.48

Name & Address Drawer 340

Well Total Depth 3430 feet

Plainville, Ks. 67663

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 171' w/130sks

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing License Number _____

Address Hays, Ks.

Company to plug at: Hour: 1:00PM Day: 12 Month: August Year: 19 88

Plugging proposal received from Kenny Brown

(company name) Same (phone) _____

were: 5 1/2" casing set at 3427' w/130 sks. Top perf at 3129';

Sq. at 960' w/250 sks and sq. at 650' to 883' w/150 sks.

Ordered 250 sks 65/35 Poz 10% Gel 2% Lite w/1/4" F.C. plus 6 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION
9/16/88
SEP 10 1988
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Company: Wichita, Kansas Hour: 2:30PM Day: 10 Month: August Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 150 sks cement w/1/4" F.C. plus 4 sks

Hulls, mixed in cement. Max 300# S.T. 250# Psi.

Pumped in 8 5/8" casing 100 sks cement w/1/4" F.C. plus 2 sks Hulls mixed in cement.

Max 400# S.T. 300# Psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
do not observe this plugging.

DATE 9-21-88

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis Hamel

INV. NO. 22350