

4-070079

11-14

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-163-23,276-00-00

W2 SW SE /4 SEC. 31, 08 S, 17 W  
660 feet from S section line  
2310 feet from E section line

Operator license# 5537

Lease: Dopita Well # A-15

Operator: Viola E. Brown  
d/b/a Kenny Brown Enterprises  
Address: 400 North Washington  
Plainville, Kansas 67663

County: Rooks 112.09

Well total depth 3449 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 207 feet

W/140 sxs.

ABAND. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD. \_\_\_\_\_, D&A \_\_\_\_\_

Plugging contractor: Viola E. Brown d/b/a Kenny Brown Enterprises License# 5537

Address: 400 North Washington - Plainville, Kansas 67663

Company to plug at: Hour: 2:00 P.M. Day: 14 Month: November Year: 1997

Plugging proposal received from: Kenny Brown Jr.

Company: Viola E. Brown d/b/a Kenny Brown Entr. Phone: 785-434-7236

Were: 5 1/2" casing set at 3446' w/250 sxs. Halliburton Mid Con II and 165 sxs EAZ.  
Cement circulated. PBTD 3415'. Perfs 3178' - 3401'.

11/20/97

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All , Part [ ], None [ ]

Completed: Hour: 3:00 P.M., Day: 14, Month: November, Year: 1997

Actual plugging report: Halliburton pumped 190 sxs or 110 bbls of Mid Con II with 2% c.c. and 500# hulls. Max. P.S.I. 1000#. S.I.P. 1000#. Pressured up annulus 500#. Cement in head. Mid Con II mixed at 11.2# per gallon.

Remarks: Cement circulated on longstring - cement in head.

Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_

Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING . Elevation: 1967 GL

I did  / did not [ ] observe the plugging.

Richard Williams  
(agent)

Form CP-2/3

INVOICED

DATE 11-21-97

INV. NO. 49557

MD