

1-28

58
R

6 - 041348

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-30183-0000

CN/2NWSE /4 SEC. 31, 8 S, 17 W
2310 feet from S section line
1980 feet from E section line

Operator license# 5537

Lease Dopita A well # 5

Operator: Kenny Brown Enterprises

County Rooks

Address: Drawer 340
Plainville, Ks. 67663

Well total depth 3425 feet ^{11.31}
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 inch @ 171 feet

Aband. oil well xx, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cmt. License#

Address: Hays, Ks.

Company to plug at: Hour: 9:00 Day: 28 Month: Jan Year: 92

Plugging proposal received from: Kenneth Brown

Company: K.B.E. phone:

Were: 5 1/2 casing set at 3424: T.D. 3425: Perf at 2896' - 3348:
Anhy - Perf at 1340: Dakota at 750: W.L.M. 3350. Top of fluid at 1600
Casing sq at 2252 w/250 sks; casing sq at 800-940 w/450 sks.
Ordered 300 sks 60/40 poz 10% gel w/1/4 lb. f.c. plus 300 lb. hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All , Part , None

Completed: Hour: 10:15AM, Day: 28, Month: Jan, Year: 92

Actual plugging report: Hooked up to 5 1/2 casing; pumped in 260 sks
60/40 poz 10% gel w/ 1/4 lb f.c. plus 500 lbs. hulls in cement. Max 750 lb.
Shut in 350 lbs. Hooked up to 8 5/8 s.p.; pumped in 40 sks 60/40 poz 10%
get w/ 1/4 lb f.c. Max 500 lbs. p.s.i. S.I. 200 lbs.

WICHITA, KANSAS
2/7/92

Remarks:
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING Elevation: GL

DATE 2-17-92 did I did not I observe the plugging.

INV. NO. 34569

Gil S.

Dennis L. Hamel
Dennis Hamel (agent)