

9-13

4-041718

15-163-01384-0000

92

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 1962

SE NE SE /4 SEC. 36, 08 S, 17 W  
1650 feet from S section line  
330 feet from E section line

Operator license# 8735

Lease: Hrabe Well # 3

Operator: S & M Oil

County: Rooks

Address: 2730 Thunderbird Dr.  
2904 Canal Blvd.  
Hays, Kansas 67601

Well total depth 147 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 90 feet  
W/60 sxs.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 12:00 P.M. Day: 13 Month: September Year 1995

Plugging proposal received from: Steve Crawford

Company: S & M Oil Phone: \_\_\_\_\_

Were: 4 1/2" casing set at 3309' w/200 sxs cement. Perf. At 3131' - 3308'.  
W.L.M. at 145'. This well was discovered by District #4 Staff to have no plugging  
information during a lease investigation. (See actual plugging report)  
Ordered 25 sxs 60/40 pozmix - 10% gel with 1/4# F.C.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All , Part [ ], None [ ]

Completed: Hour: 12:00 P.M., Day: 13, Month: September, Year: 1995

Actual plugging report: S & M Oil was asked to verify status of well condition. T.D. of well was at 145' with casing having been pulled by prior operators. S & M operators drilled to 147' and obtained cement samples for District #4 Staff. District #4 Staff concluded from cement samples that the well had most likely been plugged when casing was pulled by past operators. A new 15 sx cement plug was placed in the 8 5/8" S.P.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 25 1995 9/25/95

Remarks: Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_  
Anhy.plug: YES \_\_\_\_\_ NO \_\_\_\_\_  
Dakota plug: YES \_\_\_\_\_, NO \_\_\_\_\_  
Elevation: 1944 GL

I did  / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

Handwritten initials and marks at the bottom of the page.