

To: **6 041012**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-12
API NUMBER 15- 15-163-01385-0000
6-20-62

TECHNICIAN'S PLUGGING REPORT

Operator License # 8735
Operator: S and M Oil
Name & Address 205 N. Jefferson
Plainville, Ks. 67663

SE SE SE SEC. 36, T 8 S, R 17 W/E
_____ feet from S section line
_____ feet from E section line
Lease Name Teel Hrabe Well # 4
County _____ Rooks 108.55
Well Total Depth 3340 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 90' w/60 sks

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____
Address Russell, Ks.

Company to plug at: Hour: 9:00 A.M. Day: 12 Month: Jan Year: 19 89

Plugging proposal received from Steve Crawford
(company name) S and M Oil (phone) _____

were: 4 1/2" casing set at 3340'. Top perf at NA. Anhy 1260'. Holes in casing
from 408' to 968'. Sq w/1950 sks of cmt to cir. Ran wireline to
1083'. Top pf cement and tubing fish at 1735'. Ordered 125 sks
65/35 Poz 10% Gel 2% Lite w/1/4# F.C. plus 5 sks Hulls plus 75 sks 65/35
Poz 6% Gel w/1/4# F.C.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 PM Day: 12 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 1250'; Circ cement to surface w/125 sks A and L plus
1/4# F.C. plus 3 sks Hulls. Pulled tubing, sq from surface 75 sks 65/35 Poz 6% Gel w/1/4#
F.C. plus 2 sks Hulls mixed in cement. Max 300 psi. Shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1989 1/26/89

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 1-27-89
INV. NO. 23810
1-12

Conservation Division
Wichita, Kansas
Signed Dennis L. Hamel
(TECHNICIAN)
Dennis Hamel