

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19028-00-00
Spot: SENWSE Sec/Twnshp/Rge: 36-8S-17W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: HRABE Well Number: 5
County: ROOKS Total Vertical Depth: 3320 feet

Operator License No.: 8735

Conductor Pipe: Size feet: 8 10 7.90

Op Name: CRAWFORD, STEPHEN G. DBA S & M OI

Surface Casing: Size 8.625 feet: 110 W/65 SX CMT

Address: 1725 250TH AVE.
HAYS, KS 67601

Production: Size 4.5 feet: 3320 W/200 SX CMT
Liner: Size feet:

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/05/2002 11:30 AM

Plug Co. License No.: 3722

Plug Co. Name: CROWN WELL SERVICE INC

Proposal Rcvd. from: STEVE CRAWFORD

Company: S&M OIL

Phone: (785) 650-4003

Proposed Plugging Method: Ordered out 175 sxs 60/40 pozmix - 10% gel - 500# hulls.
Well squeezed from 815' to 2700' with 700 sxs cement.
PBTD at 2170'. FL 800'. WLTD 1535'.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/05/2002 3:30 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 1275'.
Mixed and pumped 80 sxs cement with 400# hulls.
Pulled up to 640' and circulated cement with 35 sxs and 100# hulls.
POOH. Swaged onto 4 1/2" and top staged with 15 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Annulus full of cement.

AUG 08 2002 8/8/02
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS TED HRABE #5. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 8-8-02

INV. NO. 2003060189

AUG 07 2002

ROSENCRANTZ-BEMIS # 5 HRABE 36-8-17W
SE NW SE

Contr. CO TOOLS ROOKS County

E 1904 KB Comm. 10/12 Comp. 12/13/62 IP 8 BOPD + 35% WTR/
LANS 3110-3266, GR 32

SMP Tops	Depth	Datum
ANHY	1202	+702
TOP	2788	-884
HEEB	3004	-1100
TOR	3027	-1123
KC	3047	-1143
B/KC	3291	-1387
TD	3320	-1416

Casing 8" 110 4 1/2" 3320
NO TSTS
PF 30/3110-20; 9/3154-57; 12/
3211-15; 14/3231-38; 18/3260-
66; A 7000; SWB 6 BFPH, 50%WTR

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

