

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-21,806-00-00

NW, Sec. 15, T 8 S, R 18 W/E

1320' feet from N/E section line

580' feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5537

Lease Name MADDY Well # 1

Operator Name & Address HENRY BROWN ENT.

County ROCKS

Address 410 N. WASHINGTON  
DRAWER 340  
PLAINVILLE, MISSOURI  
67663

Well Total Depth 3245 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 179

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor DREILING OIL INC. License Number 535

Address R.I. VICTORIA, MISSOURI 67671

Company to plug at: Hour: 4:30 PM Day: 16<sup>th</sup> Month: OCT Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO MERL ROGERS.

(company name) DREILING OIL INC. (phone) 913-735-2204

were: 8 5/8" - 179 FE SP. CUC ~ 1/35<sup>ST</sup> COMMON - 2% GEL - 3% CH-CL. (BY HALLIBURTON)

ORDER 190<sup>ST</sup> 50/50 FORMIX 6% GEL - 3% CH-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1<sup>ST</sup> PLUG @ 1350 FE ~ 20<sup>ST</sup> QNT. - 2<sup>ND</sup> PLUG @ 1780 FE ~ 100<sup>ST</sup> QNT.

3<sup>RD</sup> PLUG @ 240 FE ~ 40<sup>ST</sup> QNT. - 4<sup>TH</sup> PLUG - SOLID BRIDGE - HULLS - PLUG @ 40 FE ~ 110<sup>ST</sup> QNT.

10<sup>ST</sup> IN RAT HOLE - 10<sup>ST</sup> IN MOUSE HOLE. Signed M. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:45 PM Day: 16<sup>th</sup> Month: OCT Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 179 FE SP. CUC ~ 1/35<sup>ST</sup> (BY HALLIBURTON)

ORDERED 190<sup>ST</sup> 50/50 FORMIX 6% GEL - 3% CH-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1<sup>ST</sup> PLUG @ 1350 FE ~ 20<sup>ST</sup> QNT. - 2<sup>ND</sup> PLUG @ 1780 FE ~ 100<sup>ST</sup> QNT.

3<sup>RD</sup> PLUG @ 240 FE ~ 40<sup>ST</sup> QNT. - 4<sup>TH</sup> PLUG - SOLID BRIDGE - HULLS - PLUG @ 40 FE ~ 110<sup>ST</sup> QNT.

10<sup>ST</sup> IN RAT HOLE (CIR) 10<sup>ST</sup> IN MOUSE HOLE (CIR)

Remarks: DID NOT PENETRATE ARBUCHIE - CEMENTED BY HALLIBURTON

RECEIVED  
STATE CORPORATION COMMISSION  
10/26/82  
OCT 26 1982

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED  
DATE 11-9-82  
INV. NO. 1532-W

Signed M. Schmidt (TECHNICIAN)