

To: **041258**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

**11-6**  
API NUMBER 15- 163-21,859-00-00  
SE SW NE SEC. 15, T 8 S, R 18 W EX  
~~2070~~ **2110** feet from 8 section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5537  
Operator: Kenny Brown Ent.  
Name & Address 400 N. Washington  
Plainville, Ks. 67663

Lease Name Maddy Well # 2  
County Rooks 112.28  
Well Total Depth 3455 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 183 w/130 sks

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Cementing License Number \_\_\_\_\_

Address Hays, Kansas

Company to plug at: Hour: 8:00 AM Day: 6 Month: Nov Year: 19 90

Plugging proposal received from Kenny Brown

(company name) Same (phone) \_\_\_\_\_

were: 5 1/2 casing set at 3451 w/280 sks cement: perfs at 3154 to 3351; Perf anhy at 1375; perf base dakota at 750. Ordered 350 sks 65/35 poz 10% gel w/1/4 lb f.c. plus 700 lbs hulls.

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:00 PM Day: 6 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 5 1/2 casing w/310 sks cement w/1/4 lb f.c. plus

500 lbs. hulls mixed in cement. Max 500 lbs. S.I. 300 lbs. Pumped in 8 5/8 casing w/40 sks cement w/1/4 lb f.c. and 200 lbs. hulls mixed in cement. Max 300 lbs. S.I. 200 lbs.

STATE CORPORATION COMMISSION  
RECEIVED  
NOV 30 1990  
11-30-1990  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: \_\_\_\_\_

**INVOICED**  
(did / did not observe this plugging.)  
additional description is necessary, use BACK of this form.)

DATE 12-6-90  
REV. NO. 30164

*D.L.S.*

Signed Dennis L. Hamel  
(TECHNICIAN)