

4 060082

4-25

212

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-21,908-00-00  
SE NE SW, SEC. 15, T 8 S, R 18 W/EX

TECHNICIAN'S PLUGGING REPORT

1650 feet from S section line  
2970 feet from E section line

Operator License # 3517

Lease Name Kriley Well # 2

Operator: Columbian Services Corp.

County Rooks 110.18

Name & Address Band IV Tower Box 3501

Well Total Depth 3390 feet

Topeka, KS 66601-3501

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well XXXXXX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Ce Tools License Number 3517

Address \_\_\_\_\_

Company to plug at: Hour: 3:00PM Day: 25 Month: April Year: 1990

Plugging proposal received from Dick Budig

(company name) Columbian Services Corp. (phone) 913-234-0581

were: Order 100 sxs. Common and 300 sxs. 65/35 pos 8%gel.

Plug through tubing.

Note: Tbg. parted at 957'. attempted to washover and retrieve. Got to 1075' which

was below Cedar Hill sand. Developed hole problems in Sand section with sand

coming in wellbore. Impression block indicated washover pipe cutting into csg.

and headed out of hole. Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXXX Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:00PM Day: 25 Month: April Year: 1990

ACTUAL PLUGGING REPORT Ran tbg to 1073' and pumped 100sxs. common. Cement circ to surface.

Well colapsed in sand section and tbg. pulled after pressured to 1000#. Tied onto csg.

and pressured to max pressure of 1000 # and SIP of 1000#. Tied onto annulus and pmp 10

sxs. 65/35 pos 8%gel. Max pressure 400# SIP 200#. Cement didn't settle overnight and was  
at surface the next day.

Remarks: Allied Cementing  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 5-7-90

Signed Herb Deines  
(TECHNICIAN)

INV. NO. 28038 28063

Herb Deines