

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21950-00-0101
Spot: CSESENW Sec/Twnshp/Rge: 15-8S-18W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease/Unit Name: ECKART B OWWO Well Number: 1
County: ROOKS Total Vertical Depth: 3380 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

Conductor Pipe: Size feet: 8/09.85
Surface Casing: Size 8.625 feet: 241 165 SX CMT
Production: Size 4.5 feet: 3379 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/27/2002 10:00 AM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: EDWARD S. NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 800# hulls.
Well flowing, tubing parted at 2500'+.
Dakota casing leak.
Dakota 420' - 770'. Anhy. 1340'
Production Perfs 3089' -3109'.
PBTD 3288'.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/27/2002 4:15 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran impression block on tubing to 830'. Appears casing parted.
PTOH. Ran back open ended to 1475' - hard bridges - rough casing.
Allied pumped 160 sxs 60/40 pozmix - 10% gel.
Pulled tubing to 700'. Allied pumped 60 sxs cement with 250# hulls.
Pulled tubing to 300' Allied pumped 65 sxs cement with 250# hulls,
cement circulated out both 4 1/2" casing and 8 5/8" surface pipe - shut in 8 5/8".
PTOH. Squeezed with 10 sxs cement.
Max. P.S.I. 500#. Blew hole in 4 1/2" casing 3 feet down.
Topped off with 5 sxs cement. Casing full.
Note: December 30, 2002
Re-checked cement 40' from surface.

RECEIVED
JAN 03 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 1-3-03

INV. NO. 200.306/023

DEC 31 2002

STAR RESOURCES LTD
WICHITA KS 67202

15-08 -18W
SE SE NW

#1 ECKART B OWWO

site: 8 N OF PLAINVILLE KS

city: ROOKS

APR 15-163-21950

contr: UNKNOWN

well: US-183 WEST EXT (1/8 W)

well:

fr date	apd data	drng comp	card issued	last revised
07/25/80	12/04/89	12/05/89	07/25/80	07/25/90

ELV: 1932 KB LOG

tops	depth/datum
ANH	1312 +620
E/ANH	1358 +576
TOP	2864 -932
HEEB	3064 -1132
TOR	3086 -1154
LANS	3108 -1174
BKC	3326 -1394
PBTD	3351 -1419
LTD OLD	3371 -1439
RTD OLD	3380 -1448

IP status:
OIL, P 10 BO & 3 BWPD, SHAW 3089-3109, LKC 3184-3279 OA,
NOTE: INFO RELEASED: 11/17/83 - ADDED PROD FORM & ELEV; 2/28/85 - WAS OIL WELL - TIGHT HOLE
OLD INFO: OPERATOR WAS F & M OIL CO, 1-B ECKART, SPD 01/27/83, SET 8-5/8" 241.76, 4-1/2" 3379/100 SX, OIL, P 60 BO & 20 BWPD, SHAW 3089-3109 OA, (CARD ISSUED 07/21/83)
CONTR: ABERCROMBIE DRILLING
DST (1) 3085-3131 (SHAW, LKC), / 30-45-60-45, FB THRU-OUT, 200' GIP, REC 80' CLEAN GSY OIL (GR 42), 80' HO & GCM (GRIND OUT: 35% OIL, 3% G, 15% W, 47% M), 80' OIL & GCMW, (GRIND OUT: 2% OIL, 2% G, 56% W, 40% M, CHL 12,000 PPM) ISIP 913# FSIP 872#
IFP 63# -73# FFP 84# -136#

COPYRIGHT 1980
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

STAR RESOURCES LTD
WICHITA KS 67202

15-08 -18W
SE SE NW

#1 ECKART B OWWO

DST (2) 3130-3170 (LKC), / 30-45-30-45, WK 7 INCH BLO, REC 30' M, W / SO ISIP 577# FSIP 567# IFP 52# -52# FFP 52# -52#
DST (3) 3170-3185 (LKC), / 30-45-30-45, WB, DIED /7", REC 60' M, W/FEW OIL SPKS ISIP 913# FSIP 881# IFP 42# -42# FFP 52# -52# BHT 115"
DST (4) 3225-3265 (LKC), / 30-45-60-45, FB THRU-OUT, REC 190' MW ISIP 735# FSIP 703# IFP 73# -84# FFP 105# -136# BHT 110"
MICT - CO, PF (TOR) 3089-3109, W / 1 SPF, AC 750 GAL (15% MA), SWB DWN, GSO, SET 2-3/8" TBG AT 3127, POP, P 60 BO & 20 BWPD, 8/11/83
NEW INFO: FR 07/25/90, REWORKED 12/04/89 DC 12/05/89 MICT - CO, PB 3351 TD, TSTD OLD PFS (3089-3109), PF (LKC) 1/3279, 1/3205, 1/3184, AC 750 GAL (15% REG), GSO, SET 2-3/8" TBG AT 3288, POP, P 10 BO & 3 BWPD, 12/8/89, COMMINGLED