

4-042010

4-12

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-22,498-00-00

NW SW NE /4 SEC. 24, 08 S, 18 W
3630 feet from S section line
2310 feet from E section line

Operator license# 4058
Operator: American Warrior, Inc.
Address: P.O. Box 399
Garden City, Kansas 67846

Lease: Thomas Well # B-3
County: Rooks 111.64
Well total depth 3435 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 218 Feet
W/150 sxs.cmt.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Swift Services License# -

Address: P.O. Box 466 - Ness City, Kansas 67560

Company to plug at: Hour: 12:00 P.M. Day: 12 Month: April Year 1999

Plugging proposal received from: Ted Fuchs

Company: Swift Services Phone: -

Were: Ordered 145 sxs Swift Multi-Density with 500# hulls.
4 1/2" casing set at 3410' w/200 sxs cement.
Perfs at 3410' - 3435'.
D.V. Anhy at 1360' w/400 sxs.

RECEIVED
KANSAS CORPORATION COMMISSION
APR 16 1999
APR 16 1999
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 4:30 P.M. Day: 12, Month: April Year: 1999

Actual plugging report: R.U. Cementers to 8 5/8" S.P. Pressured up S.P. to 300#. Blew hole in 8 5/8" casing at 3' below braden head. Will check cement top when casing is cut off. R.U. Cementers to 4 1/2" casing. Pumped in 145 sxs cement with 500# hulls. Max. P.S.I. 2500#. S.I.P. 500#.

Remarks:

Condition of casing(in hole): GOOD ___ BAD ___ Anhy.plug: YES NO ___
Bottom plug(in place): YES ___ CALC ___, NO ___ Dakota plug: YES NO ___
Plugged through TUBING ___ CASING ___ Elevation: ___ G.L. ___

I did [X] / did not [] observe the plugging.

INVOICED

DATE APR 16 1999

INV. NO. 60847

Dennis L. Hamel
(agent)
Form CP-2/3