

15-163-01392-00-01

API NUMBER 15- 57 ✓

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SUNWSE, SEC. 24, T. 8 S, R. 18 W/E

\_\_\_\_\_ FEET FROM N/S SECTION LINE

\_\_\_\_\_ FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5135

LEASE NAME PEARL WELL # 3

OPERATOR: JOHN O FARMER  
NAME &  
ADDRESS PO BOX 352  
RUSSELL, Ks, 67665

COUNTY ROOKS

WELL TOTAL DEPTH 3425 FEET

CONDUCTOR PIPE: SIZE \_\_\_\_\_ FEET

SURFACE CASING: SIZE 8 7/8 FEET 167'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR ~~FOR~~ ALLIED CEM LICENSE NUMBER \_\_\_\_\_

ADDRESS GREAT BEND, Ks.

COMPANY TO PLUG AT: HOUR: AM DAY: 7 MONTH: 9 YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM EICHMAN

(COMPANY NAME) JOHN O FARMER (PHONE) \_\_\_\_\_

WERE: Pump 100 SX DOWN 8 7/8 ANNUBUS

Pump 25 SX CEM - 4 HULLS - 25 SX GEL - 15 X HULLS - 5 1/2 plug

125 SX CEM DOWN 5 1/2 CASING

ALLIED

50/50/22 4/16 GEL 3/4 PLUGGING PROPOSAL RECEIVED BY Sub-Scheck  
By Carl Goodrow (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 7 MONTH: 9 YEAR: 19 83

ACTUAL PLUGGING REPORT

HOOKED UP TO 8 7/8 ANNUBUS AND FLUID CIRCULATED OUT OF  
5 1/2" AND 3". HOOKED ON TO 3" TUBING AND PUMPED 100 SX CEM  
AND 11 SX GEL - HOLE BROKE OUT OF 5 1/2" AND BLEW GEL. CALLED  
FOR WELDER PUMPED 150 SX CEM AND SHUT IN.

REMARKS: TUBING - CASING WERE IN HOLE AND EATEN UP. MAX. PRESSURE  
= 200# AT SHUT IN.

I  (DID) DID NOT) OBSERVE THIS PLUGGING.

INVOICED

DATE 9-28-83

INV. NO. 5551-W

RECEIVED SIGNED Carl Goodrow  
STATE CORPORATION COMMISSION (TECHNICIAN)

SEP 12 1983  
SEP 12 1983  
CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
11 REV. 6-83