

To: **6040847**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5635

Operator: The Gene Brown Co.
Name & Address 407 S. Main
Plainville, Ks. 67663

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing License Number _____

Address Hays, Kansas

Company to plug at: Hour: 12:00PM Day: 13 Month: Jan. Year: 19 88

Plugging proposal received from Gene Brown

(company name) Same (phone) _____

were: 5 1/2" csg set at 3419' w/200 sks. Perf at 3140' - 3338'. Tbg and rods stuck at 2700'. D.V. tool at 1336' w/400 sks. Sq at 910' w/150 sks. Perf csg at 1930. Ordered 150 sks 65/35 Poz 10% Gel 2% Lite w/1/4" F.C. plus 5 sks Hulls.

Plugging Proposal Received by Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00PM Day: 13 Month: Jan Year: 19 88

ACTUAL PLUGGING REPORT Pmpd in csg 140 sks cmt w/1/4" F. C. Plus 5 sks Hulls.
Max 800# S.I. 800#. Check 8 5/8 S.P. Pressured up 700#.

Remarks: Reviewed: JAN 25, 1988

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-26-88

INV. NO. 19655

Signed Dennis L. Hamel
(TECHNICIAN)

Dennis L. Hamel

1-13-88
API NUMBER 15-163-03950-00-06
NE SE SE, SEC. 24, T 8 S, R 18 (W)E

_____ feet from S section line
_____ feet from E section line

Lease Name McMullen Well # 3

County Rooks 111.35

Well Total Depth 3426 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 263' w/175