

4-041965

4-21

API NO. 15-163-039520000

API Number: 15- - 12-09-53

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

RECEIVED
KANSAS CORP COM
MAY 11 1998
1998 APR 30

SW SW SE /4 SEC. 24, 08 S, 18 W
330 feet from S section line
2310 feet from E section line

Operator license# 31824

P. McMILLEN
Lease: ~~P. McMullen~~ Well # 1

Operator: Thomas M. Brown

County: Rooks 111.38

Address: 403 NW 3rd - P.O. Box 250
Plainville, Kansas 67663

Well total depth 3427 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 252 Feet
W/175 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 21 Month: April Year 1998

Plugging proposal received from: Thomas M. Brown

Company: Thomas M. Brown Phone: -

Were: 5 1/2" casing set at 3423' w/200 sxs cement. Perfs at 3152' - 3427'.
Anhy at 1362' w/500 sxs. Top of fish at 2210'.
Ordered 225 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls - and 10 sxs gel.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:45 P.M., Day: 21, Month: April, Year: 1998

Actual plugging report: R.I.H. with tubing to 2200'. Circulated cement to surface with 200 sxs cement with 500# hulls. P.O.O.H. with tubing and squeezed casing with 25 sxs cement. Max. P.S.I. 400#. S.I.P. 100#. 8 5/8" S.P. Cement visible at surface.

Remarks:
Condition of casing(in hole): GOOD BAD
Bottom plug(in place): YES, CALC, NO
Plugged through TUBING CASING
Anhy.plug: YES X NO
Dakota plug: YES X, NO
Elevation: G.L.

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED
MAY 04 1998

DATE

INV. NO. 50424

4-21 JUN 17 1998