

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-21, 904-00-0

NW, Sec. 24, T 8 S, R 18 W

1980 feet from N section line

990 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5562 Lease Name COLLINS Well # 1

Operator: LIBERTY ENTERPRISES, INC County ROOKS

Name & Address 308 WEST MILL PLAINVILLE, MO. 67663 Well Total Depth 3446 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 204

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated W/C # 259

Plugging Contractor PIONEER DRUG. INC. License Number 913-434-4687

Address 308 WEST MILL PLAINVILLE, MO. 67663

Company to plug at: Hour: 5:00 AM Day: 19 Month: DEC. Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO JOHN WALMER

(company name) PIONEER DRUG. CO. (phone) 913-434-4687

were: 8 5/8" - 204' SP. CMC. #130 5 1/2" 40' FORMIX - 2% GEL - 2% CA-CL (ALLIED)

ORDER - 200 5 1/2" 50' FORMIX 6% GEL - 3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 3420' #120 5 1/2" CMC. -> 2nd PLUG @ 1320' #120 5 1/2" CMC.

3rd PLUG @ 480' #100 5 1/2" CMC. -> 4th PLUG @ 240' #40 5 1/2" CMC.

5th PLUG <sup>SOLID BRIDGE</sup> HULL'S - PLUG @ 40' #0 #10 5 1/2" CMC.

10' IN RAT HOLE. (CIRCULATE) Signed [Signature] (TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 8:00 AM Day: 19 Month: DEC Year: 1982

ACTUAL PLUGGING REPORT ORDERED - 200 5 1/2" 50' FORMIX 6% GEL - 3% CA-CL. + 8 5/8" PLUG

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 3420' #120 5 1/2" CMC. 2nd PLUG @ 1320' #120 5 1/2" CMC.

3rd PLUG @ 480' #100 5 1/2" CMC. 4th PLUG @ 240' #40 5 1/2" CMC.

5th PLUG -> <sup>SOLID BRIDGE</sup> HULL'S - PLUG @ 40' #0 #10 5 1/2" CMC.

10' IN RAT HOLE (CIRCULATE) CEMENTED BY ALLIED CMC.

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 10 1983  
JAN 10 1983

I hereby certify that the above plugging instructions were given as herein stated and that I ( ~~did~~ / did not) observe this plugging.

INVOICED  
DATE 1-3-83  
INV. NO. 2299-w

Signed [Signature] (TECHNICIAN) DOIC