

6 090195

R

API NUMBER 15-163-22, 569-00-00

NE 1/4, SEC. 27, T. 8 S, R. 18 W 1/4

4950 feet from N/S section line

660 feet from N/E section line

Lease Name Lacey "A" Well # 1

County Rooks

Well Total Depth 3495 ^{113.59} feet

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8" feet 258

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Operator: F+M Oil Company, Inc.

Name & Address 422 Union Center

Wichita, Ks. 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Union Drilling Co., Inc. License Number 5103

Address 422 Union Center Wichita, Ks. 67202

Company to plug at: Hour: _____ Day: 3 Month: December Year: 19 84

Plugging proposal received from Lyle Carson

(company name) Union Drilling Co., Inc. (phone) 316-262-1872

were: Order 180 sks. 50/50 permit, 4% gel, 3% Cal. Cl. & 8 5/8" wiper plug, spot all plugs through drill pipe w/ heavy mud between all plugs.

Plugging Proposal Received by Edwin A. Schumacher
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 8:45 P.M. Day: 3 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug 3430' w/ 20 sks.

2nd plug 1365' w/ 20 sks.

3rd plug 735' w/ 1 sk. Allo-Floke & 80 sks.

4th plug 310' w/ 40 sks.

5th plug 40' solid bridge 1 sk. bulls & 10 sks. 10 sks. in rat hole

12-17-84
RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1984
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Elevation - 1985', Anhydrite - 1362', Arbuschli - 3425'
(If additional description is necessary, use BACK of this form.) (Allud)

I (did / did not) observe this plugging.

DATE 1-3-85

INV. NO. 6268

Signed Edwin A. Schumacher
(TECHNICIAN)

12-17-84
29
FORM CP-2/3
Rev. 01-84